

SCHEDULE - B

Name of the Work: Construction of drain 2nd and 3rd main RMV Extension in Ward No. 18

Indent No: 9981

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specifications. i) Lime / Cement Concrete. i. By Manual Means : A. Lime Concrete, cement concrete grade M-10 and below. MORTH Specification No 202 Page No.147. I No.18.17 PWDSR - 2013-14	Cum	97.2	240.0	Rupees Two Hundred Forty Only
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications. specification No. KBS 2.1 (b) / 2.3.5. P No 5 I No. 2.4 PWDSR - 2013-14	Cum	102	145.0	Rupees One Hundred Forty Five Only
2	Providing and laying in position plain cement concrete of mix M 75 with OPC @ 180 kgs using 40mm and down size graded granite metal CA @ 0.85 cum and FA @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM machinery, curing complete as per specifications. specification No KBS 4.1.4.2 P No. 12 I no 4.3 PWDSR - 2013-14	Cum	44.7	4000.0	Rupees Four Thousand Only
3	Providing and constructing grabute / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chiselled in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13 Page No.26. I No 5.12 PWDSR - 2013-14	Cum	100.98	4200.0	Rupees Four Thousand Two Hundred Only
4					

L. Jey
Contractor

Sl No	Description of item	Unit	Qty	In figures	In words
5	Providing and laying in position plain cement concrete of nominal mix M 15 with cement @ 240 kgs using 20mm and down size graded granite metal. CA @ 0.878 cum and FA @ 0.459 cum and machine mixed concrete laid in layers not exceeding 15 cms. Thick, well compacted in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No.12. I NO 4.6 PWDSR - 2013-14	Cum	16.83	4300.0	Rupees Four Thousand Three Hundred Only
6	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labor, curing complete as per specifications. Page No.122 I No.15.3 PWDSR - 2013-14	Sqm	224.4	70.0	Rupees Seventy Only
7	Providing and laying in position reinforced cement concrete of nominal mix M 20 with OPC @ 320 kgs with 20mm and down size graded granite metal CA @ 0.878 cum and FA @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, columns, piers, abutments, pillars, posts, sturfs, buttresses, string of lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. (excluding cost of steel, fabrication and plastering) Specification No. KBS 4.1, 4.6 Page No.12. I No 4.11 PWDSR - 2013-14	Cum	16.43	5100.0	Rupees Five Thousand One Hundred Only
8	Providing and laying position reinforced cement concrete covering slabs madeout of mix 1:1:50.3 with 20mm and down size granite metal mixed concrete laid in layers not exceeding 15cms vibrated including cost of materials, labor curing providing and laying in position including transportation complete as per specification. For 10 cms thickness slab	Sqm	270	1350.0	Rupees One Thousand Three Hundred Fifty Only
9	For 20 cms thickness slab	Sqm	21	2000.0	Rupees Two Thousand Only
10	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2.4 and finished with CM 1:3 plastering and finishing cutting etc, complete, of size 450 x 200 x 400 mm P 24 I NO 5.29.1 PWDSR - 2013-14	Nos	445	296.0	Rupees Two Hundred Ninety Six Only

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
11	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. Specification No KRBS 800.3 MORT & H Specification No 800. P No 195 I no 124.1 PWDSR - 2013-14	Sqm	54	48.0	Rupees Forty Eight Only
12	Cost of Haulage Excluding Loading and Unloading MORTH Chapter 1 (Lead chart enclosed)	Cum	180	89.35	Rupees Eighty Nine And Paise Thirty Five